

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-28008-00-00
Spot: NENWNESW Sec/Twnshp/Rge: 33-32S-14E
2327 feet from S Section Line, 3586 feet from E Section Line
Lease Name: JOHNSON Well #: 7
County: MONTGOMERY Total Vertical Depth: 1480 feet

Operator License No.: 6329
Op Name: BRIGHT, WAYNE E.
Address: 3166 CR 4000
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1480		110 SX
SURF	7	40		10 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/04/2018 12:00 AM
Plug Co. License No.: 35463 Plug Co. Name: SWS OPERATIONS LLC
Proposal Rcvd. from: WAYNE BRIGHT Company: _____ Phone: (620) 330-2891

Proposed Plugging Method: Will plugged per KCC regulations

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2018 3:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" spool hose to 1050' gelled hole and spotted 2 sack plug. Pulled up to 600' and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 16 sacks of cement with 4% gell was used to plug this well. Well was cut off and location restored.

Top	Bot	Thru	Comments
1390	1400		

RECEIVED
KCC DIST # 3
JUN 26 2018
CHANUTE, KS
DS

INVOICED
JUL 19 2018

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)