

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-28063-00-00
Spot: NENENWSE Sec/Twnshp/Rgc: 33-32S-14E
2321 feet from S Section Line, 1631 feet from E Section Line
Lease Name: JOHNSON Well #: 10
County: MONTGOMERY Total Vertical Depth: 1440 feet

Operator License No.: 6329
Op Name: BRIGHT, WAYNE E.
Address: 3166 CR 4000
INDEPENDENCE, KS 67301

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 4.5 | 1440 | | 100 SX |
| SURF | 7 | 40 | | 10 SX |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/04/2018 12:00 AM
Plug Co. License No.: 35463 Plug Co. Name: SWS OPERATIONS LLC
Proposal Rcvd. from: WAYNE BRIGHT Company: _____ Phone: (620) 330-2891

Proposed Plugging Method: Will be plugged per KCC regulations

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2018 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" spool hose to 1150' gelled hole and spotted 2 sack plug. Pulled up to 600' and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1". Ran 1" spool hose to 225' on backside of 2" and circulated cement (40 sacks) to surface. Pulled 1" and topped well off. A total of 56 sacks of cement with 4% gell was used to plug this well. Well was cut off and location restored.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1360 | 1370 | | |

RECEIVED
KCC DIST # 3
JUN 26 2018
CHANUTE, KS

DS


INVOICED
JUL 19 2018

Remarks:

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)