

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-20586-00-00
Spot: SESESWNE Sec/Twnshp/Rge: 24-34S-2E
2941 feet from S Section Line, 1329 feet from E Section Line
Lease Name: WARNER Well #: 1-B
County: SUMNER Total Vertical Depth: 3450 feet

Operator License No.: 35191
Op Name: BUFFALO OIL & GAS, LLC
Address: 102 S. RIVER ROAD PO BOX 6
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3450		150 SX
SURF	8.625	225		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/30/2018 1:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: DON SHORT Company: BUFFALO OIL & GAS, LLC Phone: (620) 218-1809

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2018 4:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP WAS SET AT 2860' AND CAPPED WITH 2 SX CEMENT. RAN WIRE LINE TO BOTTOM AND TAGGED TOP OF BOTTOM PLUG AT APPROX. 2835'. LOADED HOLE WITH FRESH WATER AND PRESSURED UP CASING TO 300 PSIG AND LET STAND FOR 15 MINS NO CHANGE IN PRESSURE. PERFORATED 4.5" AT 280' THEN CIRC. 130 SX OF 60/40 POS MIX WITH 4% GEL. 1 SX OF HULLS. HAD GOOD RETURNS. CASING STOOD FULL, JOB COMPLETE. CAME BACK FOLLOWING DAY TO CHECK TOP PLUG AND IT HAD NOT FALLEN. OPERATOR TO CUT OFF CASING WELL BELOW GROUND LEVEL.

Perfs:

Top	Bot	Thru	Comments
2915	2918	CSG	

INVOICED
JUL 19 2018

Remarks:

Plugged through: CSG

District: 02

Signed _____

Daniel Fox
(TECHNICIAN)

✓