

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-30271-00-01
Spot: SESW Sec/Twnshp/Rge: 11-20S-6W
658 feet from S Section Line, 3310 feet from E Section Line
Lease Name: UNIT A Well #: 2
County: RICE Total Vertical Depth: 3255 feet

Operator License No.: 30979
Op Name: NIGHTINGALE, RUSSELL DBA R J OPE
Address: 1044 24TH AVE
GALVA, KS 67443

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	2920		
PROD	4.5	2920		50 SX
SURF	8.625	147		170 SX

Well Type: EOR UIC Docket No: E18250.1 Date/Time to Plug: 06/04/2018 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 06/04/2018 10:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND BOTTOM TO 2900' AND CAP WITH 4 SX'S CEMENT. PERFORATE AT 850' AND 450'. RUN TUBING TO 850' AND PUMPED 5 SX'S GEL FOLLOWED BY CEMENT, GETTING CEMENT CIRCULATION TO SURFACE. PULLED TUBING OUT AND TOPPED OFF. USED APPROX. 260 SX'S.

INVOICED
JUL 19 2018

Perfs:

Top	Bot	Thru	Comments
3239	3255	OH	

Remarks: FAILED MIT INJ. WELL. COPELAND CEMENT #45861.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

✓