

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-19256-00-01
Spot: SWSESWSE Sec/Twnshp/Rge: 8-20S-1W
325 feet from S Section Line, 1767 feet from E Section Line
Lease Name: VOGTS Well #: 2
County: MCPHERSON Total Vertical Depth: 3690 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 200 W DOUGLAS, SUITE 101
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3485		100 SX
SURF	8.625	144		125 SX
TI	2.875	3540		

Well Type: SWD UIC Docket No: D12621.0 Date/Time to Plug: 06/14/2018 5:30 PM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: TANNER NELSON Company: TREK AEC Phone: (316) 201-1090

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2018 12:00 AM KCC Agent: JERRY SPARLING

Actual Plugging Report:

RAN IN 2 3/8" TUBING AND TAGGED BOTTOM @ 3485'. REMOVED 1 JOINT TO 3475'. PUMPED 50 SX 60/40 POZMIX WITH 3% CALCIUM CHLORIDE 100 LBS OF COTTONSEED HULLS. RAN WIRELINE IN TAGGED @ 3011'. PULLED TUBING TO 645'. PUMEPD 15 SX 60/40 POZMIX WITH 2% CALCIUM CHLORIDE & 50 LBS COTTON SEED HULLS @ 645'. PULLED TUBING / PUMPED OUT CELLAR. RAN TUBING BACK IN TO 250' AND PUMPED 75 SX IN CASING. RAN 1" DOWN BACKSIDE TO 150'. PUMPED 45 SX AND CIRCUALTED TO SURFACE. RAN 2 3/8" TO 155' PUMPED 45 SX AND CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3011	3485	TBG	
600	645	TBG	
120	250	CSG	

INVOICED


JUL 19 2018

Remarks: QES TICKET #55351. PLUGGED FOR FAILED MIT

Plugged through: CSG

District: 02

Signed


(TECHNICIAN)

✓