

# 15-083-10 202-0000

1060114

TO: STATE CORPORATION COMMISSION

8-4

API NUMBER 15-083-10,202-0000  
SE NW SEC. 13, T 21 S, R 24 W

CONSERVATION DIVISION - PLUGGING SECTION 3194 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3194 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME GOEBEL EAST UNIT "R" WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY HODGEMAN

OPERATOR LICENSE # 5123 WELL TOTAL DEPTH 4473 145.38 FEET

OPERATOR: PICKRELL DRILLING PRODUCTION CSG: SIZE 5 1/2" FEET 4472'

NAME AND ADDRESS 100 N. MKT. SUITE 205 SURFACE CASING: SIZE 8 5/8" FEET 312'

WICHITA, KS 67202

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 04 MONTH: 8 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MONTE

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2943

WERE: PERFS AT 4457-4463 PBTD AT 4465

1ST PLUG SANDED TO 4400'. USE DUMP BAILER TO SPOT 5 SX CEMENT ON TOP OF SAND. CUT AND RECOVER CASING. 2ND PLUG AT 1600' WITH 50 SX CEMENT, 3RD PLUG AT 800' WITH 80 SX CEMENT 4TH PLUG AT 320' WITH 40 SX CEMENT, 5TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MICHAEL MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 04 MONTH: 8 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SANDED TO 4398' AND 4 SX CEMENT, 2ND PLUG AT 830' WITH 80 SX CEMENT 3RD PLUG AT 320' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1998  
8-10-98  
CONSERVATION DIVISION  
WICHITA, KS

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 500' OF 5 1/2" CASING (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED  
I DID OBSERVE THIS PLUGGING.

SIGNED Michael Maier (TECHNICIAN) FORM CP-2/3

DATE AUG 12 1998

INV. NO. 57156