

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-01325-00-00
Spot: NESENW Sec/Twnshp/Rge: 18-8S-16W
3663 feet from S Section Line, 3021 feet from E Section Line
Lease Name: CHESNEY A-C Well #: 3
County: ROOKS Total Vertical Depth: 4496 feet

Operator License No.: 30821
Op Name: HITSCHMANN, CRAIG & RONDA DBA
Address: PO BOX 308
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3279		
SURF	8.625	87		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2018 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: CRAIG HITSCHMANN Company: HITSCHMANN, CRAIG & RONDA D Phone: (785) 885-8042

Proposed Plugging Method: Production perforations: 2815' - 3151'.
Tubing and rods stuck in hole. Worked on well for three days. Ended up with tubing at 945' and rods backed off at 1045'.
Unable to get washover pipe or taper mill below 1045'. Instant torque and losing fluid. It is possible the casing collapsed in the redbed.
Ordered 325 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2018 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 945'. Swift Services pumped 60 sx cement. Cement circulated. PTOH. Hooked up to 4 1/2" casing and pumped 145 sx cement w/100 # hulls mixed in the last 50 sx cement. Maximum pressure 600 psi. Shut in pressure 400 psi. Backside is full of cement.

GPS: 39.36074 -099.14993

INVOICED
JUL 19 2018

KCC WICHITA
JUL 02 2018
RECEIVED

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

JUN 25 2018