

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-01904-00-00
Spot: SWNWSNW Sec/Twnshp/Rge: 19-13S-14W
3453 feet from S Section Line, 3663 feet from E Section Line
Lease Name: GAYNOR Well #: 6
County: RUSSELL Total Vertical Depth: 2917 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	15	210		
PROD	7	2917		
SURF	10	804		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/04/2018 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: OCTAVIO D MORALES Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 275-2963

Proposed Plugging Method: Ordered 25 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2018 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

06/04/2018 - Dug braden head out and found 7" casing on a casing hanger full of cement. 4 1/2" casing was orange peeled to 7" casing and a 2" nipple welded in was also full of cement. Express Well Service rigged up and started to drill in 4 1/2" at the surface (sand). Drilled down to about 55' and shut down.
06/05/2018 - Ran drill collar and drilled to 100' - 110'. Shut down.
06/06/2018 - Started to drill with little to no advance in depth of well. Pulled collar out of the well. The well was plugged with ready mix cement at an early date. Swabbed hole dry.
06/12/2018 - Swift Cementing rigged up and pumped 10 sx cement. Hole stayed full.

GPS: 38.90970 -098.92299

Perfs:

INVOICED
JUL 19 2018

Remarks: SWIFT SERVICES, INC. TICKET # 27327

Plugged through: CSG

KCC WICHITA
JUL 02 2018
RECEIVED

District: 04

Signed Ray Dinkel
(TECHNICIAN)

CM

JUN 5 2018

JUN 25 2018