

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-023-21484-00-00  
Spot: SWNE Sec/Twnshp/Rge: 17-2S-37W  
1980 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: ARDENE Well #: 2-17  
County: CHEYENNE Total Vertical Depth: 4800 feet

Operator License No.: 34318

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	331		300 sx

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

Well Type: DH

UIC Docket No:

Date/Time to Plug: 06/02/2018 12:00 AM

Plug Co. License No.: 34317

Plug Co. Name: BEREDCO LLC

Proposal Rcvd. from: GILBERT

Company: BEREDCO LLC

Phone: (316) 213-0643

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS

WitnessType: NONE

Date/Time Plugging Completed: 06/02/2018 2:30 AM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @3200 w/50 sx  
2nd plug @2500 w/100 sx  
3rd plug @375 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

INVOICED  
JUL 19 2018

Remarks: QES

Plugged through: DP

KCC WICHITA  
JUL 02 2018  
RECEIVED

District: 04

Signed



(TECHNICIAN)

JUN 25 2018