

6-23
4-060700

15.009.07111.0000

30
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 9-23-43

C SW NE /4 SEC. 17, 20 S, 11 W
3300 feet from S section line
1980 feet from E section line

Operator license# - Lease: Herter "A" Well # 2

Operator: State of Kansas - Fee Fund County: Barton

Address: Kansas Corporation Commission
District #4 - Hays, Kansas 67601
R&D Oil & Gas Company #3286
Well total depth 3306 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 300 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# -

Address:

Company to plug at: Hour: 10:00A.M. Day: 23 Month June Year: 1995

Plugging proposal received from: District #4 - Hays, Kansas 67601

Company: Kansas Corporation Commission Phone: 913-628-1200

Were: Order 300 sxs. 60/40 posmix - 10% gel and hulls.

RECEIVED
STATE CORPORATION COMMISSION
7-21-95
JUL 27 1995
CONSERVATION DIVISION
WICHITA, KANSAS


Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00 P.M., Day: 23, Month: June, Year: 1995

Actual plugging report: 8 5/8" to 300'. 5 1/2" to 3206'. Dug out well head and found surface pipe orange peeled and welded to 5 1/2". Had welder cut hole and weld in collar. Perforated well at 325' - 525' - 1350'. Run tubing to 2650'. Mixed and pumped 100 sxs.cement with 200# hulls. Pulled tubing to 1325'. Pumped 70 sxs.cement with 200# hulls with cement up to 325'. Pulled tubing and tied onto production casing. Pumped 130 sxs cement with 100# hulls with cement to surface in annulus. No pressure due to weak casing at surface. Hole full of cement to surface.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.


DH (agent)