

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07114-00-00
Spot: CNWNENE Sec/Twnshp/Rge: 17-20S-11W
2310 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: HERTER B Well Number: 4
County: BARTON Total Vertical Depth: 3380 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

Conductor Pipe: Size feet: 8/09.85
Surface Casing: Size 8.625 feet: 145
Production: Size 5.5 feet: 3378
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/26/2002 2:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 265-4651

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 10% gel and hulls.
Plan to plug while pulling casing.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 12/26/2002 3:30 PM

KCC Agent: HERB DEINES

Actual Plugging Report:

8 5/8" set to 145'. 5 1/2" set to 3378'.
Squeezed holes at 1708' - 1798' with unknown amount.
Rigged up to pull casing.
Sanded to 3250' and spotted 5 sxs cement with dump bailer.
Casing parted at 4' while trying to pull slips.
Cement in annulus at 4'.
Shot hole in casing at 2490'.
Injection rate satisfactory.
Pumped 50 sxs cement followed with 150 sxs of cement with 500# hulls.
Max. P.S.I. 500#. S.I.P. 300#.


RECEIVED
JAN 03 2003 1-3-03
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

INVOICED

DATE 1-6-03

INV. NO. 2003061033

Form CP-2/3

DEC 30 2002

17-20-11W

VIRGINIA DRILLING CO. #1 HERTIER 53 17-20-11W NW NE SE

Contr. BARTON County

E 1773 Comm. Comp. 11-18-49 IP 75 BOPD

Tops	Depth	Datum	Casing
			8" 145 PB 3309
			5" 3384 PERF 24s, 3332-34
LANS	3066	-1293	ACID 500
ARB	3303	-1530	
T.D.	3384	-1611	

INDEPENDENT OIL & GAS SERVICE WICHITA, KANSAS