

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-171-20044-00-00  
Spot: SW Sec/Twnshp/Rge: 4-19S-31W  
1289 feet from S Section Line, 4002 feet from E Section Line  
Lease Name: R AND S KOHRS Well #: 1-4  
County: SCOTT Total Vertical Depth: 2789 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2789	0	WITH 150 SX CMT
SURF	8.625	367		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/05/2018 11:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TY LUNN Company: STELBAR OIL CORPORATION Phone: (316) 264-8378

Proposed Plugging Method: PUMP 25 SX CMT & 150# HULLS. LOAD & TEST CASING. PERFORATE AT 1400'. 60 SX CMT HALF IN & HALF OUT. PERFORATE AT 400'. CIRCULATE TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/05/2018 7:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

ATTEMPT TO SET CIBP. COULD NOT GET PAST 1600'. RUN TBG TO 2276' & SPOT 25 SX CMT WITH 150# HULLS. TOOH WITH TBG. TEST CASING TO 700#. PERFORATE 4 HOLES AT 1400'. INJECTION RATE 2 BPM AT 700#. PUMP 30 SX CMT FOLLOWED BY 30 SX CMT WITH 50# HULLS. DISPLACE TO 900' LEAVING 30 SX CMT INSIDE THE CASING & 30 SX CMT OUTSIDE THE CASING. PERFORATE 4 HOLES AT 900'. CIRCULATE CMT TO SURFACE WITH 140 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2757	2765		

INVOICED  
JUL 18 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
5A

(TECHNICIAN)

RECEIVED  
JUN - 8 2018  
KCC DODGE CITY