

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-02279-00-00
Spot: SWSWSWSW Sec/Twnshp/Rge: 22-33S-15E
232 feet from S Section Line, 5112 feet from E Section Line
Lease Name: BELT Well #: 4
County: MONTGOMERY Total Vertical Depth: 720 feet

Operator License No.: 34478

Op Name: STOUDT, JEAN MARIE

Address: 13606 S 128TH EAST AVE
BROKEN ARROW, OK 74011

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	700		10 SX
SURF	7	40		2 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/10/2018 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: STOUDT, JEAN MARIE

Company:

Phone: (602) 770-3260

Proposed Plugging Method: Failed CIT. Fluid coming up backside after pressure applied

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed: 05/10/2018 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 720' gelled hole and spotted 5 sack. Pulled up to 500' and spotted 5 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 35 sacks of cement with 3% gell was used to plug this well.

RECEIVED
KCC DIST # 3
JUN 26 2018
CHANUTE, KS

INVOICED *DS*

JUL 18 2018

Remarks: WELL WAS PLUGGED DUE TO FAILED CIT ON CASING.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)