

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-21983-00-00  
Spot: SESW Sec/Twnshp/Rge: 27-29S-13W  
735 feet from S Section Line, 3321 feet from E Section Line  
Lease Name: MASON Well #: 4  
County: PRATT Total Vertical Depth: 4790 feet

Operator License No.: 35186  
Op Name: SUPERNOVA ENERGY, INC.  
Address: 2250 N. ROCK RD SUITE 118-107  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3900		WITH 2 SX CMT
PROD	4.5	4760	1100	WITH 200 SX CMT
SURF	10.75	270		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2018 3:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 3900' & 2 SX CMT. PLUG AT 720' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/08/2018 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3900' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 710' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 75 SX CMT. HAD NO RETURNS. PULLED CASING UP HOLE & LET CMT SET. 5/2/18: TAG TOC @ 650' SPOT 75 SX CMT AT 300'. SPOT 40 SX CMT AT 40'. TOP OFF WITH 40 SX CMT. HOLE STILL ON VACUUM. SHUT DOWN LET CMT SET. 5/8/18: TOP OFF WELL WITH 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4209	4211		
3969	3973		

INVOICED  
JUL 18 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
MAY 10 2018  
KCC DODGE CITY