

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22411-00-01
Spot: SESENWNE Sec/Twnshp/Rge: 3-24S-5E
4249 feet from S Section Line, 1480 feet from E Section Line
Lease Name: DELL Well #: 5
County: BUTLER Total Vertical Depth: 2630 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL, PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2629		125 SX
SURF	8.625	211		160 SX

Well Type: EOR UIC Docket No: E26700.1 Date/Time to Plug: 01/30/2018 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: JOHN WASHBURN Company: Phone: (316) 265-6231

Proposed Plugging Method: As per State instructions

Plugging Proposal Received By: JONATHAN HILL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/08/2018 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1/31/2018:
1) CIBP set at 2400' and capped with 4 sks cement
2) Perforated 4.5" casing at 260'
3) Ran in hole to 250' with coiled tubing, loaded hole with water. 3 bbls to break circulation.
4) Pumped 65 sks of 60/40/4% cement with hulls. No returns up 4.5", lost returns on backside. Tied onto backside and pumped water to displace cement past squeeze holes
5) Wait 2 hrs. Ran back in with coiled tubing and tagged cement at 320. Loaded hole with .5 bbls and circulate water up back side.
6) Pulled coiled tubing up to 250' and pumped 145 sks of 60/40/4% cement up 4.5".
7) Pulled coild tubing out of hole, tied into 4.5" casing and pumped cement -- circulated cement up backside of 4.5" casing.

2/5/2018:
- plug fell >100' inside 4.5" casing. Tagged backside at approx. 20'.

2/8/2018:
1) Ran in colied tubing and tagged at 250'
2) Pumped 35 sks of 60/40/4% cement, circulated cement to surface. Topped off backside with cement. Hole staying full

Perfs:

Top	Bot	Thru	Comments
2496	2510		

INVOICED
JUL 18 2018

Remarks: CEMENTING COMPLETED BY GRESSELL OILFIELD SERVICES/COPELAND. TICKET #S: 45028 AND 45038

Plugged through: TBG