

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-22566-00-00
Spot: NESESWNW Sec/Twnshp/Rge: 3-21S-11W
3058 feet from S Section Line, 4111 feet from E Section Line
Lease Name: SNIDER F Well #: 1
County: STAFFORD Total Vertical Depth: 3327 feet

Operator License No.: 30886
Op Name: THOMAS, JOHN R. DBA VAMCO OPER
Address: 265 AVENUE K
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3319	0	WITH 150 SX CMT
SURF	8.625	240		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2018 11:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOHN THOMAS Company: VAMCO OPERATIONS Phone: (620) 793-2604

Proposed Plugging Method: SAND BACK TO 3270' & TOP WITH 4 SX CMT. PRESSURE TEST CASING. PEFORATE AT 600' & CIRCULATE CMT INSIDE & OUT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2018 6:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SAND BACK ATTEMPTED. APPROXIMATELY 200# SAND WAS DUMPED IN CASING. BAILER TO DUMP CMT WOULD NOT GO DOWN HOLE. TBG WAS RIH TO 3200' WHERE 30 SX CMT WAS PUMPED. PULL TBG TO 2000' & PUMP 15 SX CMT. POOH WITH TBG. PERFORATE AT 600'. TIH WITH TBG TO 600' & PUMP 140 SX CMT TO FILL 4 1/2" CASING & ANNULUS TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3319	3327		OH

INVOICED
JUL 19 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY GRESSEL OILFIELD SERVICE.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
JUL - 2 2018
KCC DODGE CITY

Form CP-2/3

KMS