

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-165-21985-00-00  
Spot: SENENW Sec/Twnshp/Rge: 14-16S-20W  
4298 feet from S Section Line, 2995 feet from E Section Line  
Lease Name: LEGLEITER 'A' Well #: 1-14  
County: RUSH Total Vertical Depth: 4030 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4013	0	WITH 175 SX CMT
SURF	8.625	1420		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/12/2018 11:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT & 150# HULLS. PRESSURE TEST CASING TO 500#. PERFORATE AT 1450' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/12/2018 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO PERFORATIONS & PUMPED 25 SX CMT, THE 25 SX CMT WITH 150# HULLS. PULLED TBG & TESTED CASING TO 500#. PERFORATED AT 1450'. TIED ONTO THE CASING & CIRCULATED CMT TO SURFACE WITH 300 SX CMT. HOLE STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
3573	3577		


INVOICED  
JUL 19 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed  (TECHNICIAN)

RECEIVED  
JUN 18 2018  
KCC DODGE CITY 

*lms*