

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-21729-00-00
Spot: NENESWSE Sec/Twnshp/Rge: 24-16S-20W
1276 feet from S Section Line, 1618 feet from E Section Line
Lease Name: HART Well #: 1
County: RUSH Total Vertical Depth: 3884 feet

Operator License No.: 34134
Op Name: TREK RESOURCES, INC.
Address: 4925 GREENVILLE AVE., STE 915
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	1335		WITH 185 SX CMT
PROD	5.5	3883	0	WITH 150 SX CMT
SURF	8.625	217		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2018 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 35 SX CMT & 150# HULLS. SPACER TO 1350. CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2018 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

PUMPED 73 BBL WATER AHEAD TO MAKE SURE WE COULD PUMP INTO IT. MIXED 35 SX CMT & 150# HULLS, 51 BBL SPACER THEN 150 SX CMT. PRESSURED TO 600#. SHUT IN WITH 300#. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 600#.

Top	Bot	Thru	Comments
3484	3494	CSG	

INVOICED
JUL 19 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JUN 26 2018
KCC DODGE CITY

Form CP-2/3

KMS