

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-19405-00-00
Spot: NWNWSWSE Sec/Twnshp/Rge: 5-24S-14E
1200 feet from S Section Line, 2340 feet from E Section Line
Lease Name: PHIL BIRK Well #: 2
County: WOODSON Total Vertical Depth: 1742 feet

Operator License No.: 32044
Op Name: TRIMBLE & MACLASKEY OIL LLC
Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 4.5 | 1734 | | 25 SX |
| SURF | 0 | 0 | | 0 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2018 9:00 AM
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC
Proposal Revd. from: TRIMBLE & MACLASKEY Company: _____ Phone: (62) 083-6200

Proposed Plugging Method: Cement Plug at 1142 ft on top of old equipment in holePerf at 450 ft and 250 ftCement plug at 450 ft Cement plug at 250 ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2018 11:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1140' two set sof fishing tools below 1140',pumped 15 sxs cement @ 1140', pulled tubing to 450', pumped 15 sxs cement,pulled tubing to 250', pumped 40 sxs cement to surface,gel spacers between cement plugs,casing shot @ 250' & 450'.

RECEIVED
KCC DIST # 3
JUN 11 2018
CHANUTE, KS

MH

INVOICED
JUL 19 2018

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern

(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3948**
 Foreman Rick Ledford
 Camp Eureka KS

API # 15-207-19405

| | | | | | | | |
|---------------------------|------------|---------------------|---------|-----------|--------|---------|-------|
| Date | Cust. ID # | Lease & Well Number | Section | Township | Range | County | State |
| 6-7-18 | 1000 | Phil Birk # 2 | 5 | 24 | 14E | Woodson | KS |
| Customer | | | Unit # | Driver | Unit # | Driver | |
| Trumble & Macksey Oil LLC | | | 105 | Dave G. | | | |
| Mailing Address | | | 115 | Josiah H. | | | |
| D.O. Box 171 | | | | | | | |
| City | State | Zip Code | | | | | |
| Cridley | KS | 66822 | | | | | |

Safety Meeting
 RL
 OG
 JP

Job Type P.T.A. old well Hole Depth _____ Slurry Vol. _____ Tubing 1" hydriil
 Casing Depth _____ Hole Size _____ Slurry Wt. 14 # Drill Pipe _____
 Casing Size & Wt. 3 1/2" inside 9 5/8" Cement Left in Casing _____ Water Gal/SK 2.0 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting - Rig up to 1" hydriil Plugging order as follows:
15 sks @ 1140'
15 sks @ 450'
40 sks @ 250 to surface (inside & out of 3 1/2")
gel-spacers between plugs
"Thank You"

| Code | Qty or Units | Description of Product or Services | Unit Price | Total |
|-------------|--------------|---|------------|---------|
| C1052 | 1 | Pump Charge | 500.00 | 500.00 |
| C107 | 0 | Mileage <u>2nd call of 2</u> | 3.95 | n/c |
| C203 | 70 sks | <u>60/40 Perm cement</u> | 12.25 | 857.50 |
| C206 | 240 # | <u>470 gel</u> | .20 | 48.00 |
| C108A | 3.01 | <u>ton mileage bulk fuel</u> | n/c | 345.00 |
| C206 | 150 # | <u>gel-spacers</u> | .20 | 30.00 |
| INVOICED | | | | |
| JUL 19 2018 | | | | |
| | | | Subtotal | 1815.50 |
| | | | Sales Tax | |

Authorization by Brian Macksey Title _____ Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.