

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-00616-00-00
Spot: SENESENE Sec/Twnshp/Rge: 5-24S-14E
3498 feet from S Section Line, 224 feet from E Section Line
Lease Name: PHIL BIRK Well #: 4
County: WOODSON Total Vertical Depth: 1702 feet

Operator License No.: 32044
Op Name: TRIMBLE & MACLASKEY OIL LLC
Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1685		30 SX
SURF	8	22		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC
Proposal Revd. from: TRIMBLE & MACLASKEY Company: _____ Phone: (620) 836-2000

Proposed Plugging Method: Cement plug at 1240 ft on top of old tools in holePerf at 450ft and 250ftCement plug at 450 ftCement at 250 ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: _____ KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1225', collapsed casing below, pumped 20 sxs cement, pulled tubing to 450', pumped 20 sxs cement, pulled tubing to 250' pumped 80 sxs cement to surface, gel spacers between cement plugs, casing shot@ 250' & 450'.

RECEIVED
KCC DIST # 3
JUN 11 2018
CHANUTE, KS

MT

INVOICED
JUL 1 8 2018

Remarks:

Plugged through: TBG

District: 03

Signed Mitch Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3947**
 Foreman Rick Ledford
 Camp Eureka KS

API# 15-207-00616

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-7-18	1000	Phil Rick #4	5	24	14E	Wagoner	Ks
Customer			Unit #	Driver	Unit #	Driver	
Trumble + Macloskey Oil LLC			105	Dave G.			
Mailing Address			115	Jason H.			
P.O. Box 171							
City	State	Zip Code					
Gridley	Ks	66852					

Safety Meeting
 RL
 OG
 JH

Job Type D.T.A. old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth _____ Hole Size _____ Slurry Wt. 14# Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK 2.0 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting - Rig up to 2 3/8" tubing. Plugging order as follows:
20 SKS @ 1225'
20 SKS @ 450'
80 SKS @ 250 to surface (inside & out of 4 1/2")
gel-spacers between plugs
"Thank You!"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	30	Mileage 1# well of 2	3.95	118.50
C203	120 SKS	(100) 40 Permox cement	12.75	1530.00
C206	410#	400 gal	.20	82.00
C108A	5.16	tan mileage back to rk	69.16	345.00
C206	200#	gel-spacers	.20	40.00
C214	20#	pulls (bottom plug)	.45	9.00
INVOICED				
JUL 19 2018				
			Subtotal	2874.50
			Sales Tax	

Authorization by Brian Macloskey Title _____ Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.