

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25997-00-00
Spot: SWNWSENW Sec/Twnshp/Rgc: 3-20S-24W
3407 feet from S Section Line, 3685 feet from E Section Line
Lease Name: LANE TRUST Well #: 1-3
County: NESS Total Vertical Depth: 4500 feet

Operator License No.: 34876
Op Name: TRIPLE CROWN OPERATING LLC
Address: 2201 S. UTICA PL STE 100
TULSA, OK 74114

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4325		WITH 2 SX CMT
PROD	5.5	4497	1626	WITH 280 SX CMT
SURF	8.625	219		WITH 160 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/11/2018 3:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Revd. from: PRESTON DREILLING Company: DREILING EXPLORATION Phone: (785) 621-6021

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS WITH 2 SX CMT. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 750' WITH 80 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2018 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4325' WITH 2 SX CMT. 1ST PLUG AT 1600' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 750' WITH 80 SX CMT. 3RD PLUG AT 250' WITH 50 SX CMT. 4TH
PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4388	4394		
4374	4384		

INVOICED
JUL 19 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILFIELD.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JUN 14 2018
KCC DODGE CITY

KMS