

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-047-21627-00-00  
Spot: N2N2SENE Sec/Twnshp/Rge: 33-25S-16W  
3706 feet from S Section Line, 642 feet from E Section Line  
Lease Name: CUDDL WITH ME Well #: 1  
County: EDWARDS Total Vertical Depth: 4789 feet

Operator License No.: 34886  
Op Name: TOTO ENERGY, LLC  
Address: 25815 OAK RIDGE DR  
SPRING, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4340		WITH 2 SX CMT
COND	13.375	55		WITH 85 SX CMT
PROD	5.5	4791	2020	WITH 250 SX CMT
SURF	8.625	317		WITH 505 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/09/2018 8:30 AM  
Plug Co. License No.: 34422 Plug Co. Name: RED ROCK ENERGY SERVICES INC.  
Proposal Rcvd. from: TIM MYERS Company: TOTO ENERGY Phone: (603) 724-1675

Proposed Plugging Method: CIBP @ 4340' WITH 2 SX CMT. PLUG AT 1080' WITH 10 SX GEL & 50 SX CMT. PLUG AT 375' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/09/2018 10:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4340' WITH 2 SX CMT. 1ST PLUG AT 1056' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 379' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED BUT FELL. TOPPED OFF WITH 70 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4402	4405		
4388	4392		

INVOICED  
JUL 19 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
MAY 15 2018  
KCC DODGE CITY