

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-21631-00-00
Spot: NENWNWNW Sec/Twnshp/Rge: 27-29S-9E
4963 feet from S Section Line, 4909 feet from E Section Line
Lease Name: DAVES Well #: D21
County: ELK Total Vertical Depth: 2435 feet

Operator License No.: 32874
Op Name: VEEM JADE OIL & GAS LLC
Address: 11417 S GRANITE AVE
TULSA, OK 74137

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2350		
PROD	4.5	2435		150 SX
SURF	7	65		40 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/26/2018 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KEVIN WARDLOW Company: _____ Phone: (620) 330-3666

Proposed Plugging Method: 20 sacs on bottom, 10 sacs per intermediate plugs with gel spacers and 500 foot to surface

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 06/06/2018 11:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated casing at 500'. Washed 2" to 2325' gelled hole and spotted 20 sack plug. Pulled up to 1510' and spotted 10 sack plug. Pulled up to 507 and circulated cement to surface. Pulled 2" and topped well off. A total of 142 sacks of 60/40 pozmix with 4% gel was used to plug this well.

Perfs:

Top	Bot	Thru	Comments
2198	2209		

RECEIVED
KCC DIST #3
JUN 12 2018
CHANUTE, KS

DS
INVOICED
JUL 19 2018

Remarks: WELL WAS PLUGGED DUE TO FAILED CIT ON THIS WELL.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)