

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-26958-00-00  
Spot: NESE Sec/Twnshp/Rge: 21-29S-18E  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: WOOLERY, LARRY Well #: 21-2  
County: NEOSHO Total Vertical Depth: 1193 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1193		145 SX
SURF	8.625	22		5 SX
TI	2.375	1120		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2018 2:30 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/14/2018 2:30 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to TD and the well pumped full of cement from btm to top thru the cement string. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, 112 sacks of portland cement were used to plug well. The production pipe was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
1098	1101		
1046	1048		
1040	1042		
819	821		
782	785		
758	760		
679	683		
667	671		

RECEIVED  
KCC DIST # 3  
JUL 02 2018  
CHANUTE, KS  
INVOICED  
JUL 18 2018 AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)