

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-27618-00-00
Spot: NENENENE Sec/Twnshp/Rge: 20-28S-19E
165 feet from N Section Line, 165 feet from E Section Line
Lease Name: STICH, WILLIAM A Well #: 20-7
County: NEOSHO Total Vertical Depth: 800 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	794		120 SX
SURF	8.625	22		5 SX
T1	2.375	767		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2018 2:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 06/06/2018 2:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was ran to 790 feet and the well pumped full of cement from btm to top. The cement string was pulled to 200 feet and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, a total of 98 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
640	646		
RECEIVED KCC DIST # 3 JUN 15 2018 CHANUTE, KS AD INVOICED JUL 18 2018			

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)