

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-27636-00-00
Spot: SWSENE Sec/Twnshp/Rge: 20-28S-19E
1260 feet from N Section Line, 450 feet from E Section Line
Lease Name: STICH, WILLIAM A Well #: 20-10
County: NEOSHO Total Vertical Depth: 770 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	766		100 SX
SURF	8.625	23		5 SX
TI	2.375	738		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2018 10:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 06/06/2018 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

According to operator, a cement string was lowered to 770 ft and the well pumped full of cement from btm to top thru the cement string. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, 98 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
638	644		

RECEIVED
KCC DIST # 3
JUN 19 2018
CHANUTE, KS

INVOICED *AD*
JUL 18 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)