

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-23635-00-00
Spot: SWNESE Sec/Twnshp/Rge: 7-31S-18E
1993 feet from S Section Line, 552 feet from E Section Line
Lease Name: PHILLIPS, R. DALE Well #: 7-4
County: LABETTE Total Vertical Depth: 1045 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1043		120 SX
SURF	8.625	22		4 SX
TI	2.375	844		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 05/02/2018 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: _____ Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 05/02/2018 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Circulate cement through tubing from 1040' to surface. Pull tubing up to 200', pump 4 bbls. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography. 98 Total sacks cement pumped.

Perfs:

Top	Bot	Thru	Comments
394	600		
368	572		

RECEIVED
KCC DIST # 3
MAY 22 2018
CHANUTE, KS

RH

INVOICED
JUL 18 2018

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)