

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-24034-00-00
Spot: W2E2SWSW Sec/Twnshp/Rge: 8-31S-18E
660 feet from S Section Line, 700 feet from W Section Line
Lease Name: PHILLIPS, R. DALE Well #: 3-8
County: LABETTE Total Vertical Depth: 1113 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1095		143 SX
SURF	8.625	21		5 SX
T1	2.375	1020		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 05/02/2018 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: _____ Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 05/02/2018 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Circulate cement through tubing from 1050' to surface. Pull tubing up to 200', pump 4 bbls. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography. 112 Total sacks cement pumped.

Perfs:

Top	Bot	Thru	Comments
996	998		
941	943		
934	936		
666	669		
645	647		
603	608		
576	580		

INVOICED
JUL 18 2018

RECEIVED
KCC DIST # 3
MAY 22 2018
CHANUTE, KS

RH

Remarks:

Plugged through: TBG

District: 03

Signed

Russell Hine

(TECHNICIAN)