

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-25761-00-00  
Spot: SWSENE SW Sec/Twnshp/Rge: 22-29S-18E  
1583 feet from S Section Line, 2031 feet from W Section Line  
Lease Name: 4D LAND & CATTLE COMPAN Well #: 22-3  
County: NEOSHO Total Vertical Depth: 1202 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING. LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1200		170 SX
SURF	8.625	20		4 SX

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/17/1982 1:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE. LLC  
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 205-8510

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 04/17/1982 1:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 1150 ft. The well was pumped full of cement thru the cement string. The cement string was pulled to 200 ft and the well again pumped full of cement. The cement string was removed and the well pumped full. The well was cut off below plow depth and the location restored. According to operator, a total of 182 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
658	1092		Coals OA

RECEIVED  
KCC DIST # 3  
JUN 08 2018  
CHANUTE, KS

AD

INVOICED  
JUL 18 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)