

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-25909-00-00  
Spot: SWNESESW Sec/Twnshp/Rge: 32-28S-18E  
823 feet from S Section Line, 2035 feet from W Section Line  
Lease Name: POWERS, PATTIE Well #: 1-32  
County: NEOSHO Total Vertical Depth: 1245 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1211		170 SX
SURF	8.625	20		4 SX

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/12/2018 1:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Revd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 06/12/2018 1:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A cement string was lowered to TD and the well pumped full of cement from btm to top thru the cement string. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, a total of 112 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KCC DIST # 3  
JUL 02 2018  
CHANUTE, KS

AD

INVOICED

JUL 18 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning  
(TECHNICIAN)