

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-27018-00-00
Spot: SWNESWSW Sec/Twnshp/Rge: 15-29S-18E
896 feet from S Section Line, 900 feet from W Section Line
Lease Name: THORNTON, DAVID M. Well #: 15-4
County: NEOSHO Total Vertical Depth: 1150 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1150		150 SX
SURF	8.625	22		5 SX
T1	2.375	1094		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 06/14/2018 9:30 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: PARTIAL
Date/Time Plugging Completed: 06/14/2018 9:30 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to TD and the well pumped full of cement from bun to top thru the cement string. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, 112 sacks of portland cement were used to plug well. The production pipe was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
1051	1054		
997	999		
992	994		
778	780		
740	743		
718	720		
636	640		
623	627		

INVOICED

JUL 18 2018

RECEIVED
KCC DIST # 3
JUL 02 2018
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)