

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-27264-00-00
Spot: SWNESWSW Sec/Twnshp/Rge: 8-28S-16E
661 feet from S Section Line, 664 feet from W Section Line
Lease Name: MUSTAIN, DON Well #: 8-1
County: WILSON Total Vertical Depth: 1312 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1307		190 SX
SURF	8.625	23		5 SX
T1	2.375	1089		

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 04/30/2018 9:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 04/30/2018 9:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 1200 ft and the well pumped full of cement from btm to top. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, a total of 126 sacks of portland cement were used. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
1047	1049		
1010	1012		
979	981		
940	943		
927	929		
852	856		
840	844		

INVOICED
JUL 18 2018

RECEIVED
KCC DIST # 3
MAY 17 2018
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning

(TECHNICIAN)