

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-133-27168-00-00  
Spot: NENWSWNW Sec/Twnshp/Rge: 25-27S-18E  
1625 feet from N Section Line, 600 feet from W Section Line  
Lease Name: PARISH, WANDA Well #: 25-1  
County: NEOSHO Total Vertical Depth: 1080 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1060		106 SX
SURF	8.625	25		5 SX

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2018 10:30 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Revd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 04/26/2018 10:30 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A cement string was lowered to 900 ft and the well pumped full of cement from btm to top thru the cement string. The cement sting was pulled to 200 ft and the well again pumped full of cement. The cement string was removed and the well topped off with cement. According to operator, 84 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KCC DIST # 3  
MAY 24 2018  
CHANUTE, KS

AD

INVOICED

JUL 18 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning  
(TECHNICIAN)