

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-21546-00-00  
Spot: SWNWSESW Sec/Twnshp/Rge: 22-11S-32W  
904 feet from S Section Line, 1414 feet from W Section Line  
Lease Name: BEAGLEY TRUST Well #: 1-22  
County: LOGAN Total Vertical Depth: 4662 feet

Operator License No.: 33268  
Op Name: RL INVESTMENT, LLC  
Address: 2698 J O TERRACE  
HILL CITY, KS 67642

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		165 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/08/2018 12:00 AM  
Plug Co. License No.: 35410 Plug Co. Name: STP DRILLING LLC  
Proposal Rcvd. from: KIRBY Company: STP DRILLING LLC Phone: (785) 421-7036

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 05/08/2018 12:15 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @2975 w/50 sx  
2nd plug @1700 w/100 sx  
3rd plug @275 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx

INVOICED  
JUL 18 2018

Remarks: SOS

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

KCC WICHITA

MAY 31 2018

RECEIVED

MAY 11 2018