

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-20028-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 16-34S-15E  
4151 feet from S Section Line, 337 feet from E Section Line  
Lease Name: RIPLEY Well #: 11A  
County: MONTGOMERY Total Vertical Depth: 470 feet

Operator License No.: 33782  
Op Name: ROCK PETROLEUM LLC  
Address: PO BOX 22  
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	470		0 SX
SURF	8	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: BOB SIGL Company: \_\_\_\_\_ Phone: (620) 306-1405

Proposed Plugging Method: Run 1" to bottom, cement to surface, pull 1" out, top off cement, cut well head off 4' below ground level, restore location.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 06/19/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 448' gelled hole and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped inside of casing off. Ran 1" down backside to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 51 sacks of cement with 3% gell were used to plug this well. Well was cut off and location restored.


Perfs:

RECEIVED  
KCC DIST # 3  
JUN 27 2018  
CHANUTE, KS

DS

INVOICED  
JUL 18 2018

Remarks:  
Plugged through: TBG

District: 03 Signed   
(TECHNICIAN)