

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-01209-00-00
Spot: SESWNENE Sec/Twnshp/Rge: 16-34S-15E
4194 feet from S Section Line, 711 feet from E Section Line
Lease Name: RIPLEY Well #: 3
County: MONTGOMERY Total Vertical Depth: 1110 feet

Operator License No.: 33782

Op Name: ROCK PETROLEUM LLC

Address: PO BOX 22
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	1110		0 SX
SURF	10	20		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug:

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Revd. from: BOB SIGL

Company:

Phone: (620) 306-1405

Proposed Plugging Method: Run 1" to bottom, cement to surface, pull 1" out, top off cement, run 1" down backside, cement to surface, pull " out, top off cement, cut well head off 4' below ground level, restore location.

Plugging Proposal Received By: DUANE SIMS

Witness Type: PARTIAL

Date/Time Plugging Completed: 06/20/2018 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 470' gelled hole and spotted 2 sack plug. Pulled up to 225' and pumped 40 sacks of cement. Ran out of cement. Came back next day and ran inside 2" to 225'. Also ran 1" down backside to 225'. Circulated cement to surface inside and outside casing. Pulled 1" and topped well off. A total of 122 sacks of cement with 3% gell were used to plug this well. Well was cut off and location restored.

RECEIVED
KCC DIST # 3
JUN 27 2018
CHANUTE, KS

DS

INVOICED


JUL 18 2018

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)