

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-01207-00-00
Spot: SESENE Sec/Twnshp/Rge: 16-34S-15E
4051 feet from S Section Line, 54 feet from E Section Line
Lease Name: RIPLEY Well #: 1B
County: MONTGOMERY Total Vertical Depth: 1150 feet

Operator License No.: 33782
Op Name: ROCK PETROLEUM LLC
Address: PO BOX 22
CANEY, KS 67333

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	1150		0 SX
SURF	10	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: BOB SIGL Company: _____ Phone: (620) 306-1405

Proposed Plugging Method: Run 1" tubing to bottom, cement to surface, pull 1" out, top off cement, cut well head off 4' below ground level, restore location.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 06/19/2018 9:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 350' pumped 80 sacks of cement. Pulled 1". Came back the next day and ran 1" down inside of 2" to 225'. Circulated cement to surface. Pulled 1" and topped inside of casing off. Ran 1" down backside to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 140 sacks of cement with 3% gell were used to plug this well. Well was cut off and location restored.

Perfs:

RECEIVED
KCC DIST # 3
JUN 27 2018
CHANUTE, KS

DS

INVOICED
JUL 18 2018

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)