

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21063-00-00
Spot: N2SWNWNW Sec/Twnshp/Rge: 28-15S-34W
800 feet from N Section Line, 330 feet from W Section Line
Lease Name: DEANNA E Well #: 1-28
County: LOGAN Total Vertical Depth: 4650 feet

Operator License No.: 3293
Op Name: RUSSELL OIL, INC.
Address: PO BOX 8050
EDMOND, OK 73083

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4639		150 SX
SURF	8.625	269		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2018 9:00 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: TODD BROWN Company: RUSSELL OIL, INC. DBA Phone: (785) 445-6720

Proposed 8 5/8" surface casing set at 269' w/180 sx cement.
Plugging 5 1/2" production casing set at 4639' w/150 sx cement.
Method: Port Collar set at 2427' w/475 sx cement.
TD 4650'. PBD 4597'.
Perforations: 4368' - 4371', 4495' - 4498' and 4538' - 4540'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2018 11:50 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4350' and pumped 1500 # gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 2400' and pumped 115 sx cement w/100 # hulls. Pulled tubing to 1200' and pumped 115 sx cement w/50 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 15 sx cement. Connected to 8 5/8' surface casing and pumped 5 sx cement. Pressured to 300 #.

GPS: 38.72731N -101.11246W

Perfs:

Top	Bot	Thru	Comments
4538	4540		
4495	4498		
4368	4371		

INVOICED
JUL 18 2018

Remarks: OUTLAW WELL SERVICE LLC PULLING UNIT AND QUALITY OILWELL CEMENTING TICKET # 744

Plugged through: TBG

District: 04

Signed Darrel Dipman
KCC WICHITA (TECHNICIAN) CM

APR 20 2018

MAY 17 2018

RECEIVED