

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21662-01-00
Spot: SWSESWSE Sec/Twnshp/Rge: 13-33S-18W
203 feet from S Section Line, 1751 feet from E Section Line
Lease Name: JAMES 3318 Well #: 1-13H
County: COMANCHE Total Vertical Depth: 5175 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5110		WITH 50 SX CMT
COND	20	130		WITH 12 SX CMT
L1	4.5	9550		TOP OF LINER 5151'
PROD	7	5614	1728	WITH 225 SX CMT
SURF	9.625	833		WITH 820 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/07/2018 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-5752

Proposed Plugging Method: SET CIBP @ 5110' WITH 50 SX CMT. PLUG AT 870' WITH 100 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/07/2018 2:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5110'. CIRCULATED HOLE WITH 180 BBL MUD THEN SPOTTED 50 SX CMT ON TOP OF CIBP. 1ST PLUG AT 870' WITH 100 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED.

INVOICED
JUL 18 2018

Perfs:

Top	Bot	Thru	Comments
8320	8612		
7920	8200		
7520	7860		
7004	7408		
6610	6940		
6120	6502		
5780	6117		
5360	5722		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. TMD= 9550'

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
MAY 15 2018
KCC DODGE CITY