

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20593-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 32-32S-19W
1939 feet from S Section Line, 1947 feet from W Section Line
Lease Name: BIRD Well #: 1-32
County: COMANCHE Total Vertical Depth: 5300 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5066		WITH 10 SX CMT
PROD	4.5	5298	0	WITH 450 SX CMT
SURF	8.625	615		WITH 650 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/14/2018 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5066' WITH 10 SX CMT. PLUG AT 1000' WITH 100 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 05/14/2018 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5066'. CIRCULATED HOLE WITH 85 BBL MUD THEN SPOTTED 10 SX CMT ON TOP OF CIBP. FOUND THE SURFACE CASING ORANGE-PEELED TO THE PRODUCTION CASING. PERFORATED AT 1000' & ESTABLISHED CIRCULATION AT 2 BBL PER MINUTE AT 450#. PUMPED 150 SX CMT & DISPLACED TO 450'. WAITED 2 HOURS ON CMT. TAGGED CMT AT 510'. TOPPED OFF THE 4 1/2" CASING WITH 5 SX CMT. RAN 1" DOWN THE ANNULUS FROM 64' TO SURFACE WITH 15 SX CMT. HOLE STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5116	5225	CSG	

INVOICED
JUL 18 2018

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed  (TECHNICIAN)

RECEIVED
MAY 23 2018
KCC DODGE CITY