

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20987-00-01
Spot: SWSWSENE Sec/Twnshp/Rge: 24-33S-20W
2319 feet from N Section Line, 1221 feet from E Section Line
Lease Name: BAKER FARMS A Well #: 1
County: COMANCHE Total Vertical Depth: 6080 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5142		WITH 10 SX CMT
CIBP		5240		
CIBP		5390		
PROD	4.5	6082	1506	WITH 235 SX CMT
SURF	8.625	688		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/10/2018 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5142' WITH 2 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 250' WITH 70 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2018 10:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5142'. CIRCULATED THE HOLE WITH 80 BBL MUD THEN SPOTTED 10 SX CMT ON TOP OF THE CIBP. 1ST PLUG AT 1000' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 70 SX CMT. CMT CIRCULATED BUT FELL. TOPPED OFF WITH AN ADDITIONAL 56 SX CMT BUT ORR ENTERPRISES WILL ONLY SHOW 70 SX CMT FOR THE TURNKEY JOB.

Perfs:

Top	Bot	Thru	Comments
5200	5203		
5192	5196		

INVOICED
JUL 18 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
MAY 15 2018
KCC DODGE CITY