

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21235-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 5-31S-19W
361 feet from S Section Line, 4927 feet from E Section Line
Lease Name: ZIELKE Well #: 5-1
County: COMANCHE Total Vertical Depth: 5250 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4978		WITH 10 SX CMT
COND	20	70		
PROD	4.5	5245	1912	WITH 180 SX CMT
SURF	8.625	675		WITH 350 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/17/2018 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4978' WITH 10 SX CMT. PLUG AT 1130' WITH 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: HEITH WALSH WitnessType: NONE
Date/Time Plugging Completed: 05/17/2018 2:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 4978'. CIRCULATED THE HOLE WITH 75 BBL MUD THEN SPOTTED 10 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1130' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5028	5072	CSG	

INVOICED
JUL 18 2018

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Heith Walsh
(TECHNICIAN)

RECEIVED
MAY 22 2018
KCC DODGE CITY