

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-24047-01-00
Spot: S2S2SWSW Sec/Twnshp/Rge: 23-34S-10W
200 feet from S Section Line, 660 feet from W Section Line
Lease Name: BETH 3410 Well #: 1-23H
County: BARBER Total Vertical Depth: 4727 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5100		WITH 50 SX CMT
COND 20		40		WITH 10 SX CMT
LI		9224		5340-9224
PROD 7		5421	1504	WITH 300 SX CMT
SURF	9.625	860		WITH 425 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2018 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: AARON YANCEY Company: SANDRIDGE EXPLORATION Phone: (405) 429-5752

Proposed Plugging Method: SET CIBP @ 5100' WITH 50 SX CMT. PLUG AT 900' WITH 100 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 06/05/2018 9:45 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5100'. LOAD HOLE WITH MUD. SPOT 50 SX CMT ON TOP OF CIBP THROUGH TBG. 1ST PLUG AT 900' WITH 100 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8825	9113		
8433	8740		
8066	8344		
7758	8018		
7338	7635		
7013	7255		
6562	6914		
6206	6464		
5868	6120		
5523	5780		
5082	5286		

INVOICED

JUL 18 2018

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. TMD = 9224'.

Plugged through: TBG

District: 01

RECEIVED
JUN 13 2018
KCC DODGE CITY

Signed Kenny M. Sullivan
SA (TECHNICIAN)