

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-21654-01-00  
Spot: SESWSESE Sec/Twnshp/Rge: 26-33S-17W  
172 feet from S Section Line, 664 feet from E Section Line  
Lease Name: WARREN 3317 Well #: 1-26H  
County: COMANCHE Total Vertical Depth: 5127 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5300		WITH 50 SX CMT
COND	20	120		WITH 9 SX CMT
	L1 4.5	9786		TOP OF LINER @ 3319'
PROD	7	5621	1409	WITH 250 SX CMT
SURF	9.625	750		WITH 420 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/22/2018 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5300' WITH 50 SX CMT. PLUG AT 3419' WITH 25 SX CMT. PLUG AT 780' WITH 100 SX CMT. PLUG AT 330' WITH 30 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/22/2018 9:35 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5300'. CIRCULATED THE HOLE WITH 150 BBL MUD THEN SPOTTED 50 SX CMT ON TOP OF CIBP. 1ST PLUG AT 3419' (TOP 100' OF 4 1/2" LINER) WITH 25 SX CMT. 2ND PLUG AT 780' WITH 100 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
8400	8766		
7951	8314		
7499	7863		
7047	7411		
6596	6959		
6144	6507		
5692	6055		
5240	5603		

INVOICED  
JUL 18 2018

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. TMD= 9786'

Plugged through: TBG

District: 01

Signed [Signature]  
SA (TECHNICIAN)

RECEIVED  
MAY 25 2018  
KCC DODGE CITY