

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-24063-01-00
Spot: S2S2S2SE Sec/Twnshp/Rge: 26-34S-10W
200 feet from S Section Line, 1320 feet from E Section Line
Lease Name: LUKINS 3410 Well #: 1-26H
County: BARBER Total Vertical Depth: 4780 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5400		WITH 50 SX CMT
COND 20		80		WITH 14 SX CMT
L1	4.5	8200		5509-8200 NO CMT
PROD 7		5625	1742	WITH 330 SX CMT
SURF	9.625	956		WITH 455 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/25/2018 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: AARON YANCEY Company: SANDRIDGE EXPLORATION & PR Phone: (405) 429-5752

Proposed Plugging Method: CIBP @ 5400' WITH 50 SX CMT. PLUG AT 990' WITH 100 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 05/25/2018 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5400'. CIRCULATE HOLE WITH MUD. SPOT 50 SX CMT ON TOP OF CIBP THROUGH TBG. 1ST PLUG AT 900' WITH 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8027	8146		
7733	7970		
7499	7650		
7198	7416		
6931	7116		
6648	6854		
6244	6560		
5964	6150		
5669	5898		
5246	5450		

INVOICED

JUL 18 2018

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Kenny M. Sullivan
57A

(TECHNICIAN)

RECEIVED
MAY 31 2018
KCC DODGE CITY