

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-007-24064-01-00
 Spot: SESESWSE Sec/Twnshp/Rge: 26-34S-10W
200 feet from S Section Line, 1340 feet from E Section Line
 Lease Name: LUKINS 3410 Well #: 2-26H
 County: BARBER Total Vertical Depth: 4726 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5400		WITH 50 SX CMT
COND 20		80		WITH 14 SX CMT
L1		9470		5593-9470
PROD 7		5732	1786	WITH 340 SX CMT
SURF 9.625		867		WITH 455 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/30/2018 8:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Rcvd. from: AARON YANCEY Company: SANDRIDGE EXPLORATION & PR Phone: (405) 429-5752

Proposed Plugging Method: CIBP @ 5400'. PLUG AT 900' WITH 100 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
 Date/Time Plugging Completed: 05/30/2018 5:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5400'. LOAD HOLE WITH MUD & SPOT 50 SX CMT ON TOP OF CIBP.
 1ST PLUG AT 900' WITH 100 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD
 PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
9173	9385		
8723	9000		
8338	8648		
7970	8276		
7636	7888		
7218	7550		
6846	7122		
6538	6746		
6123	6430		
5768	6048		
5350	5550		

INVOICED
JUL 18 2018

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
 MAY 31 2018
 KCC DODGE CITY

Signed Kenny M. Sullivan
 (TECHNICIAN)