

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21810-01-00  
Spot: SWSESWSW Sec/Twnshp/Rge: 17-35S-7W  
300 feet from S Section Line, 880 feet from W Section Line  
Lease Name: BERNICE Well #: 2-17H  
County: HARPER Total Vertical Depth: 5345 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		10 sx cement
	11 7	5345		200 sx cement
	L1 4.5	9950		300 sx cement
PROD	7	5345	1310	
SURF	9.625	788		380 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2018 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-5835

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/08/2018 5:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4835' ON TUBING. BP RELEASED 180 BBLs OF MUD FOLLOWED BY 50 SKS OF CEMENT WAS SPOTTED ON THE BP. THE CASING WAS RECOVERED FROM 1310' & LAYED OUT. TUBING WAS RUN TO 1300' WHERE 50 SKS OF CEMENT WAS SPOTTED. PULLED TUBING TO 900' & SPOTTED 50 SX CEMENT. PULL TUBING TO 300' & CIRCULATED HOLE FULL WITH 110 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
8272	8719		
7717	8163		
7161	7608		
6606	7052		

INVOICED  
JUL 18 2018

Remarks: CLASS "C" CEMENT. ORR ENTERPRISES. TMD = 10,999

Plugged through: TBG

District: 02

Signed [Signature] DISTRICT SUPERVISOR  
(TECHNICIAN)