

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-20789-00-02  
Spot: N2SESWNE Sec/Twnshp/Rge: 23-14S-15W  
2190 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: NIEDENTHAL Well #: 10  
County: RUSSELL Total Vertical Depth: 3215 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3214		100 SX
SURF	8.625	207		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2018 10:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: SCHECK OIL OPERATIONS Company: SCHECK, TIMOTHY DBA SCHECK Phone: (785) 483-4096

Proposed Plugging Method: Ordered 280 sx 60/40 pozmix 4% gel cement, 8 sx gel and 400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 05/23/2018 12:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 3100' and pumped 8 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 1500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 500'. Circulated with 75 sx cement. Topped off with 25 sx cement. Pumped 5 sx cement into backside. Shut in pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
3205	3207		

INVOICED  
JUL 18 2018

Remarks:

Plugged through: TBG

District: 04

Signed CASE MORRIS  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

JUN 04 2018

JUN 12 2018 6-12-18

CONSERVATION DIVISION  
WICHITA, KS