

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25617-00-00
Spot: E2E2SE Sec/Twnshp/Rge: 21-17S-13W
1320 feet from S Section Line, 330 feet from E Section Line
Lease Name: SCHNEIDER Well #: 2
County: BARTON Total Vertical Depth: 3408 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 211 S FRONT ST
RUSSELL, KS 67665

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3467 | 1462 | 135 SX |
| SURF | 8.625 | 454 | | 200 SX |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/11/2018 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM SCHECK Company: SCHECK, TIMOTHY DBA SCHECK Phone: (785) 483-4096

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/11/2018 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 1462'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 450' and pumped 50 sx cement w/100 # hulls. Pulled casing to 200'. Circulated cement to surface with 75 sx cement. Pulled casing and hole stayed full.

GPS: 38.55433 -098.75803

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3405 | 3406 | | |

INVOICED
JUL 18 2018

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CM

KCC WICHITA

MAY 31 2018

RECEIVED

MAY 15 2018