

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-20654-00-00
Spot: S2S2NW Sec/Twnshp/Rge: 6-11S-33W
2970 feet from S Section Line, 1350 feet from W Section Line
Lease Name: DUMLER Well #: 1-6
County: LOGAN Total Vertical Depth: 4676 feet

Operator License No.: 3988
Op Name: SLAWSON EXPLORATION COMPANY,
Address: 204 N ROBINSON AVE STE 2300
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4799		470 SX
SURF	8.875	343		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2018 1:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: GREG WYATT Company: SLAWSON EXPLORATION COMPA Phone: (580) 816-0417

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/850 # hulls.
8 5/8" surface pipe set at 343' w/200 sx cement.
4 1/2" production casing set at 4799' w/125 sx cement. Stage collar set at 2675' w/345 sx cement.
TD 4800', PBTD 4753'.
Perforations: 4306' - 4309' and 4644' - 4646'. Lower set reported to have been squeezed with 50 sx cement by Rodney Gonzales.
Casing leak near 3960'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2018 3:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

CIBP set at 4280'. Ran tubing to 4260' and pumped 92 sx cement w/250 # hulls. Pulled tubing to 2850' and pumped 92 sx cement w/250 # hulls. Pulled tubing to 1430' and pumped 80 sx cement w/250 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 60 sx cement. Pressured to 300 #.

GPS: 39.12725N -101.02972W

Perfs:

Top	Bot	Thru	Comments
4644	4646		
4306	4309		

INVOICED

JUL 18 2018

Remarks: FRITZLER TRUCKING INC. SERVICE UNIT AND GLOBAL CEMENTING SERVICE TICKET # 3300

Plugged through: TBG

District: 04

Signed

Darrel Dipman

KCC WICHITA

(TECHNICIAN)

CM

MAY 01 2018

MAY 17 2018

RECEIVED